# BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2012-13/RD/WORK_INDENT4555/CALL-2

## APPROVED SCHEDULE - B

**No.EE/BTP/BBMP/E-PMT/04/2014-15, Date:17.06.2014**

**Improvements of Drains & construction of cement concrete road at Devingara & Muneshwara layout in ward no. 8, Kodigehalli sub division**

| Sl. No. | Approved Qty. | Description | Unit | Approved Tender Rates of ASWATHNARAYAN ANJANAPPA | |
|---|---|---|---|---|---|
| | | | | In Figures | In Words |
| 1 | 73.8 | KSRRB 300-1. Earth work excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. No. 150/ Item No. 19.1.1/ PWD SR 2012-13. | Cum | 60.0 | Rupees Sixty Only |
| 2 | 708.48 | Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 2012-13 | Sqm | 50.0 | Rupees Fifty Only |
| 3 | 708.48 | Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 24/ Item No. 5.33/ PWD SR 2012-13 | Sqm | 70.0 | Rupees Seventy Only |
| 4 | 177.12 | Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete (P.No.28 Item No.5.31.1) 7.5 cms thick. SR-2012-13 | Sqm. | 350.0 | Rupees Three Hundred Fifty Only |
| 5 | 196.8 | KSRRB 300-3. Earthwork excavation and foming in embankment by manual means in ordinary soil with initial lead upto 15 m. and lift of 1.5m. (When earth is taken from bank cutting or from borrow pits ) including breaking of clods, spreading to required line and level, forming, and cost of all labour complete as per specifications. (excluding watering and compaction of earth ) ( P 150, I.No. 19.3) SR-2012-13 | Cum | 80.0 | Rupees Eighty Only |
| 6 | 1312 | KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (P. 158, I.No. 19.64) SR-2012-13 | Sqm | 10.0 | Rupees Ten Only |
| 7 | 131.2 | KSRRB 300-64.2. Extra for watering the earth to bring the earth upto required optimum moisture content with mechinery including cost of all labour, HOM of machineries complete as per specifications. (P. 159, I.No. 19.72) SR-2012-13 | Cum | 50.0 | Rupees Fifty Only |
| 8 | 131.2 | KSRB 4-1.3: Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.57cummachine mixed machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation and plinth including cost of all materials labour HOM of machinery curing complete as per specifications (P. No. 12, Item No. 4.3) 2012-13 SR | Cum | 3500.0 | Rupees Three Thousand Five Hundred Only |

Exe. Engr.
Btp. Dn.

| | | | | | |
|---|---|---|---|---|---|
| 9 | 131.2 | KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of nominal mix 1:1.5:3 with 20mm and down size graded granite metal, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintles, retaining walls, return walls, walls (any thickness ) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing, complete as per specifications. (excluding cost of steel, fabrication & plastering) (Page No. 13, Item No. 4.11) SR 2012-13 | Cum | 5200.0 | Rupees Five Thousand Two Hundred Only |
| 10 | 1312 | Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift. ( P. 187 I. No. 22.7) SR-2012-13 | Sqm | 80.0 | Rupees Eighty Only |
| 11 | 116 | Providing groove cutting for width of 5mm to 10mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade,coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. for concrete pavement( P. 188 I. No. 22.8.1) SR-2012-13 | Rmtr | 30.0 | Rupees Thirty Only |
| 12 | 270.6 | Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km ( Page No.141) | Cum | 80.0 | Rupees Eighty Only |

**Signature of the Contractor**

**Executive Engineer**
**Byarayanapura Division**
**BBMP, Bangalore - 92**